Sika Corporation Construction

October 18, 2010

Coverdeck Systems, Inc. 305 East Ayre Street Newport, DE 19804

Attn: Mr. Paul Betty Fax: 302-427-7582

Re: Coverdeck System / Sikalastic RoofPro Membrane System

Dear Mr. Betty,

Upon review of informatiojn and samples provided, for the Coverdeck System, it is Sika's opinion that the Coverdeck would be compatible to properly applied and fully cured, Sikalastic RoofPro Membrane Systems.

Some key installation factors/conditions for placement of the covering over the Sika system would include:

- 1. No mechanical fasteners being used.
- 2. No assemblies that could jeopardize the integrity of the Sikalastic system (no sharp objects).
- 3. Proper drainage exists to prevent moisture entrapment.

Therefore, Sika would stand behind a properly installed and fully cured, Sikalastic system, provided it was not compromised by a covering/topping or its installation procedures.

Regards,

David Axt

LAM Tech Field Services Manager

Construction Division

Cc: Tom Zuppa – Sika Corporation Wayne Ellis – Sika Corporation

